Construcciones El Samán, C.A.
RIF: J-00000000-0
Email: contacto@ejemplo.com
Phone: +58 212 000 0000
Web: www.ejemplo.com
Address: Main Avenue, Muestra Business Centre, 1st floor, Office 10

ESTIMATE

Full apartment refurbishment — 120 m2

Project address: 7th floor, Apartment 7-B, Los Álamos Residences, Caracas
Date: 08/15/2026

Client

Name: Familia Rodríguez
Country: Venezuela
Offer validity: 30 days
Currency: USD (US$)
Estimate No. P-2026-001

PROPOSAL SUMMARY

TOTAL	OFFER VALIDITY	DATE	CURRENCY
40,648.31 USD	30 days	08/15/2026	USD

EXECUTIVE SUMMARY OF THE PROPOSAL (BREAKDOWN BY CHAPTERS)

Project Chapter	Subtotal	Weight (%)
PRELIMINARIES AND DEMOLITION	2,670.25 USD	7.6 %
WALLS AND PARTITIONS	3,328.00 USD	9.5 %
FLOOR AND WALL TILING	11,106.40 USD	31.7 %
KITCHEN	8,460.00 USD	24.1 %
BATHROOMS	2,243.00 USD	6.4 %
SERVICES (PLUMBING AND ELECTRICAL)	3,780.00 USD	10.8 %
PAINTING AND FINISHES	3,454.00 USD	9.9 %

PRELIMINARIES AND DEMOLITION — 2,670.25 USD

Line item	Quantity	Price	Amount
1.1 Demolition of internal partitions			
Demolition of internal concrete block partitions up to 20 cm thick, by hand, without affecting the stability of the adjoining structural elements. Includes loading and removal of waste and debris.	**30.50 m2**	**18.50 USD/m2**	**564.25 USD**
Living room – kitchen	18.00 m2	18.50 USD/m2	333.00 USD
Main bathroom	7.50 m2	18.50 USD/m2	138.75 USD
Guest bathroom	5.00 m2	18.50 USD/m2	92.50 USD

1.2 Removal of existing floor and wall finishes

Lifting of existing ceramic floor and wall finishes by hand and removal of the material to a licensed tip.	**138.00 m2**	**12.00 USD/m2**	**1,656.00 USD**
Floors	96.00 m2	12.00 USD/m2	1,152.00 USD
Kitchen and bathroom walls	42.00 m2	12.00 USD/m2	504.00 USD

1.3 Protection of surfaces and site cleaning

Protection of areas that remain in use, erection of light-duty scaffolding and general site cleaning, including removal of waste and debris.	**1.00 ea**	**450.00 USD/ea**	**450.00 USD**

WALLS AND PARTITIONS — 3,328.00 USD

Line item	Quantity	Price	Amount

2.1 Partition in 15 cm hollow concrete block

Construction of internal partitions in 15 cm vibrated hollow concrete block laid in cement mortar, including setting out, plumbing and light-duty scaffolding.	**28.00 m2**	**46.00 USD/m2**	**1,288.00 USD**
Kitchen partition	12.50 m2	46.00 USD/m2	575.00 USD
Main bathroom partition	9.00 m2	46.00 USD/m2	414.00 USD
Guest bathroom partition	6.50 m2	46.00 USD/m2	299.00 USD

2.2 Cement render to walls

Cement mortar render to vertical surfaces up to 10 mm thick, ruled and with angles and arrises formed, measured over the whole surface, ready for decoration.	**84.00 m2**	**17.50 USD/m2**	**1,470.00 USD**
Total	84.00 m2	17.50 USD/m2	1,470.00 USD

2.3 Crack repair and levelling of surfaces

Cutting out and making good cracks and fissures, application of structural mortar and levelling of existing surfaces before the final finish.	**60.00 m2**	**9.50 USD/m2**	**570.00 USD**
Total	60.00 m2	9.50 USD/m2	570.00 USD

FLOOR AND WALL TILING — 11,106.40 USD

Line item	Quantity	Price	Amount

3.1 Large-format rectified porcelain floor tiling

Supply and laying of 90x90 cm rectified porcelain tiles bedded in C2 TE cementitious adhesive with back-buttering, 2 mm joints pointed with epoxy grout. Includes levelling of the substrate and wet cutting.	**108.00 m2**	**68.00 USD/m2**	**7,344.00 USD**
Total + extra for cutting	108.00 m2	68.00 USD/m2	7,344.00 USD

Quoted product:

26.50 USD / m2 *Rectified porcelain tile 90x90 cm*

3.2 Lacquered MDF skirting

Supply and fixing of 10 cm matt white lacquered MDF skirting, bonded with grab adhesive and perimeter-sealed with silicone.

88.00 m | **9.80 USD/m** | **862.40 USD**

Total + extras	88.00 m	9.80 USD/m	862.40 USD

3.3 Wall tiling in 60x120 cm porcelain

Internal wall tiling in large-format tiles, thin-bed with back-buttering in C2 TE S1 adhesive. 3 mm joints pointed with epoxy grout. Excludes special pieces.

50.00 m2 | **58.00 USD/m2** | **2,900.00 USD**

Kitchen (between units)	12.00 m2	58.00 USD/m2	696.00 USD
Main bathroom	22.00 m2	58.00 USD/m2	1,276.00 USD
Guest bathroom	16.00 m2	58.00 USD/m2	928.00 USD

Quoted product:

24.00 USD / m2 *Polished porcelain tile 60x120 cm*

KITCHEN

8,460.00 USD

Line item	Quantity	Price	Amount

4.1 Supply and installation of kitchen units

Installation of kitchen units (base and wall units) in high-pressure melamine with soft-close ironmongery. Includes levelling, fixing and adjustment of doors and drawers.

6.80 m | **690.00 USD/m** | **4,692.00 USD**

Base and wall units	6.80 m	690.00 USD/m	4,692.00 USD

4.2 Quartz worktop

Supply and installation of polished quartz worktop with square edge and sealed joints, cut out for sink and hob.

6.80 m | **460.00 USD/m** | **3,128.00 USD**

Worktop	6.80 m	460.00 USD/m	3,128.00 USD

Quoted product:

295.00 USD / m *Blanco Norte quartz, subtle veining*

4.3 Kitchen plumbing

Installation of hot and cold water services in PPR pipework, with isolating valves and new PVC sanitary waste for sink and dishwasher. Material included.

1.00 ea | **640.00 USD/ea** | **640.00 USD**

BATHROOMS

2,243.00 USD

Line item	Quantity	Price	Amount

5.1 Shower tray installation

Supply and bedding of shower tray with waste, connection to the drainage system, fixing and silicone sealing. Fully installed and tested.

2.00 ea | **324.00 USD/ea** | **648.00 USD**

5.2 WC and washbasin installation

Supply and installation of porcelain WC and washbasin with brassware, connections, tested and in working order.

Quoted product:

380.00 USD / ea *Porcelain sanitaryware set*

2.00 ea	480.00 USD/ea	960.00 USD

5.3 Toughened glass shower screen

Supply and installation of toughened glass shower screen with framing, fixing to walls and silicone sealing.

2.00 ea	317.50 USD/ea	635.00 USD

SERVICES (PLUMBING AND ELECTRICAL) — 3,780.00 USD

Line item	Quantity	Price	Amount

6.1 General plumbing installation

Replacement of the hot and cold water distribution in PPR pipework, with isolating valves and PVC sanitary waste. Includes watertightness testing.

1.00 ea	1,350.00 USD/ea	1,350.00 USD

6.2 Electrical installation (lighting points and sockets)

Installation of circuits, consumer unit with protective devices, cabling and accessories (switches and socket outlets) to the layout drawing. Includes functional testing.

1.00 ea	1,450.00 USD/ea	1,450.00 USD

6.3 Supply and installation of LED light fittings

Supply and installation of recessed and decorative LED light fittings, with connection, testing and certification of operation.

1.00 ea	980.00 USD/ea	980.00 USD

PAINTING AND FINISHES — 3,454.00 USD

Line item	Quantity	Price	Amount

7.1 Painting of internal walls

Painting of vertical surfaces in premium matt emulsion, two coats over a priming coat, with making good of minor defects and rubbing down between coats.

260.00 m2	8.90 USD/m2	2,314.00 USD
Walls	260.00 m2	8.90 USD/m2	2,314.00 USD

7.2 Painting of ceilings

Painting of ceilings in premium matt emulsion, two coats over a priming coat.

120.00 m2	9.50 USD/m2	1,140.00 USD
Ceilings	120.00 m2	9.50 USD/m2	1,140.00 USD

TAXABLE BASE	35,041.65 USD
• Selected products and materials	**6,828.00 USD (19,5 %)**
• Labor, resources and execution of the works	**28,213.65 USD (80,5 %)**
VAT (16.0 %)	5,606.66 USD
ESTIMATE TOTAL	**40,648.31 USD**

The breakdown distributes the taxable base among the chosen products and materials and the rest of the work (labor, resources and execution of the works). Percentages are calculated on that same taxable base.

Scope and additional information

Sample document generated with CotizaT: the company, the client, the site address and all amounts are fictitious and do not refer to any real person or company.
Includes skilled labour, first-quality materials and full project management. Excludes furniture, soft furnishings and air-conditioning equipment.

Commercial terms

Payment terms: 40% deposit to start, 35% at 50% certified progress and 25% on handover.
Estimated programme: 12 weeks from signature.
12-month warranty on installations and finishes (see the warranty table).

PROJECT WARRANTIES

Warranty periods on the **execution and installation** of the works included in this estimate, grouped by type of work. Materials, lighting, fixtures and equipment retain their manufacturer's warranty.

STRUCTURE, PARTITIONS AND MASONRY — 5 years

Execution of the structure, reinforcement, walls, partitions, rendering and masonry. Includes workmanship cracking. Does not cover settlement of the existing building or structural movement outside the works contracted.

FLOORING, PAVING AND WALL TILING — 5 years

Laying of porcelain, ceramic, stone, marble, timber flooring and skirting: adhesion, levelling and joints. The material keeps its manufacturer's warranty.

TIMBER JOINERY (DOORS, CLOSETS, CABINETRY) — 3 years

Assembly, fitting hardware, squareness and finish of doors, closets, walk-in wardrobes and bespoke cabinetry. Excludes extreme ambient humidity, impact and wear from use.

ALUMINIUM, PVC AND GLASS JOINERY — 3 years

Sealing, squareness and operation of windows, shower screens and sliding doors. Toughened glass and branded hardware follow the manufacturer's warranty.

PLUMBING AND SANITARY INSTALLATIONS — 5 years

Installation: pipework, joints, wastes and water outlets (watertightness and operation). Taps, basins, WCs, showers and other fittings: manufacturer's warranty.

ELECTRICAL AND LIGHTING — 5 years

Installation: circuits, boards, containment and lighting points. Luminaires, wiring accessories (switches, sockets) and electronic equipment: manufacturer's warranty.

PLASTER, DRYWALL AND CEILINGS — 3 years

Fixing, jointing and flatness of plasterboard and drywall partitions and ceilings. Excludes damp from leaks outside our scope and impact damage.

PAINTING AND SURFACE FINISHES — 2 years

Adhesion and uniformity of applied paint, stucco and varnishes. Does not cover dirt, later damp, direct sun without maintenance or touch-ups from use.

MIRRORS, GLASS AND DECORATIVE HARDWARE — 2 years

Fixing and sealing of mirrors, decorative glass and hardware installed. Breakage by impact is excluded.

APPLIANCES, SANITARYWARE AND WHITE GOODS (INSTALLATION) — 2 years

Assembly and connection of sanitaryware, taps and equipment supplied and installed by us. The product keeps its manufacturer's warranty.

The warranty covers defects in the execution and installation of the works included in this estimate, from the formal handover of the works. Materials and equipment keep their manufacturer's warranty. Excluded are misuse, lack of maintenance, work carried out by third parties, leaks or movement of the existing property, and normal wear and tear. Any claim will be handled in writing and, where applicable, the defective work will be repaired or replaced at no charge.

BY THE CONSTRUCTION COMPANY

Construcciones El Samán, C.A.
RIF: J-00000000-0

ACCEPTED BY THE CLIENT

Familia Rodríguez
Signature of Conformity / Date